

Takhini River Bridge Deck Replacement

Km 1468.9 Alaska Highway #1, Yukon 2006-2007

TRAFFIC ACCOMODATION BULLETIN

- Anticipated construction period is from 01 May to 31 July 2006
- One lane of the bridge will be closed to traffic during construction
- Available traffic lane will be 3.3 m (10'-10) wide during Stage 1 and 4.0 m (13'-1) wide during Stage 2
- No restriction on vehicle height during Stage 1 or Stage 2
- Height of temporary center-line barrier will be 0.5 m (1'-8) above the deck
- During concrete pour, traffic will be guided across the bridge by a pilot vehicle at a restricted speed of 5 km/h
- Maximum delay of 30 minutes for public traffic
- Stakeholders will be informed through media announcements at least a week in advance of scheduled concrete pour
- Full legal load will be allowed during construction and any load restriction will be conveyed to stakeholders through media announcements well in advance
- A written request at least 10 working days in advanced of scheduled travel will be required for oversize and overweight trucks
- Traffic is required to follow the speed restriction signs, signals and other warning signs

Dated: 6 July 2006